



General Engineering Contractors – Excavating, Paving, Grading

525 JACOBY STREET □ SAN RAFAEL, CA 94901 □ TELEPHONE (415) 454-7011

FAX (415) 454-8376 STATE CONTRACTORS LICENSE #132128

CHANGE ORDER REQUEST

Date:	02/28/17	Job Number:	16408
To: City of San Pablo 13831 San Pablo Avenue San Pablo, CA 948060		Project:	San Pablo Pavement Rehab North Arlington Slide Repair
Attn: Barbara Hawins		COR #:	004
Fax or e-mail #: BarbaraH@sanpabloc.a.gov		GBI EW #:	
		Owner RFP/PCO#:	

Explanation:

GBI is pleased to provide the below pricing for the North Arlington Emergency Slide Repair. This pricing is based upon the City of San Pablo Plans by Miller Pacific for North Arlington Dated 2/7/17. GBI proposes to start work by March 13th (pending weather) to install a new stitch pier reinforcing wall and pavement section. The will include the below items of work.

Cost:

<u>Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Price</u>	<u>Amount</u>
1) Traffic Control, Equipment Mobilization, Pothole, USA, Remove AC Prior to Drill	LS	1	\$ 33,350.00	\$ 33,350.00
2) 24" diameter Piers - 26' Deep - 13 EA - 6' O.C. and seventy-five foot - 3' x 2' Grade Beam with Curb	LS	1	\$ 122,856.00	\$ 122,856.00
3) New Asphalt - Grind 10" Existing AC, Place 6" AB II with 4" of HMA Pavement 1200SF. Grind 2" AC and Repave - 900 SF	LS	1	\$ 28,125.00	\$ 28,125.00
Total Cost				\$ 184,331.00

By reason of this extra work, contract time will be extended:

15-20

Days

Note: GBI does not perform extra work without written authorization.

Submitted by:

Trevor Nuccio

Date:

02/28/17

Accepted by:

Date: